

ULTRANIXX

CENTRAL AIR BY GREE-KINGHOME



Flexible

Side discharge, small footprint, **24VAC** compatible

Comfortable

Quiet operation, optimal performance
from **-22°F** to **129°F**

Efficient

Up to **20 SEER/10.5 HSPF**

Adjustable

2/3 and **4/5 ton** outdoor unit options



ENERGY
EFFICIENT



QUIET
OPERATION



EASY
INSTALLATION



SMALL
FOOTPRINT



ULTRA
PERFORMANCE

	ULTRANIXX	BOSCH INVERTER DUCTED SPLIT SYSTEM IDS 2.0	DAIKIN FIT	FUJITSU HALCYON MPAH	RHEEM CLASSIC PLUS RP**17	MITSUBISHI PVA / PUZ-AH*	CARRIER 40MBAQ* / 38MARBQ* & 38MBRBQ*
CAPACITY	24K - 60K (FIELD CONFIGURABLE)	24K - 60K (FIELD COMFIGURABLE)	18K - 60K (INDIVIDUAL UNITS)	24K - 48K (INDIVIDUAL UNITS)	24K - 48K (INDIVIDUAL UNITS)	24K - 42K (INDIVIDUAL UNITS)	24K - 48K (INDIVIDUAL UNITS)
EFFICIENCY	UP TO 20 SEER / 10.5 HSPF	UP TO 20.5 SEER / 10.5 HSPF	UP TO 18 SEER / 10.0 HSPF	UP TO 19 SEER / 10.7 HSPF	UP TO 19 SEER / 10.7 HSPF	UP TO 19 SEER / 11.2 HSPF	UP TO 20 SEER / 11.6 HSPF
HEATING RANGE	-22°F TO 75°F	-4°F TO 86°F	-20°F TO 70°F	-5°F TO 75°F	-5°F TO 75°F	-13°F TO 75°F	-22°F TO 86°F
COOLING RANGE	5°F TO 129°F	15°F TO 125°F	0°F TO 115°F	-5°F TO 115°F	-5°F TO 115°F	0°F TO 115°F	-22°F TO 130°F / -13°F TO 122°F
FLEXIBLE SIZING OF OUTDOOR UNIT	24/36K OR 48/60K (FIELD CONFIGURABLE)	24/36K OR 48/60K (FIELD CONFIGURABLE)	18/24/30/36/42/48/60K (INDIVIDUAL UNITS)	24/30/36/48K (INDIVIDUAL UNITS)	24/30/36/48K (INDIVIDUAL UNITS)	24/30/36/42K (INDIVIDUAL UNITS)	24/36/48K (INDIVIDUAL UNITS)
24VAC INTERFACE	YES (FACTORY INSTALLED)	YES (FACTORY INSTALLED)	NO (PROPRIETARY CONTROL REQUIRED)	YES (FIELD INSTALLED OPTION)	YES (FIELD INSTALLED OPTION)	YES (FIELD INSTALLED OPTION)	YES (FIELD INSTALLED OPTION)
OUTDOOR UNIT DISCHARGE DESIGN	HORIZONTAL	VERTICAL	HORIZONTAL	HORIZONTAL	HORIZONTAL	HORIZONTAL	HORIZONTAL
SMALL, NARROW FOOTPRINT OF OU	YES	NO	YES	YES	YES	YES	YES
SOUND LEVEL OF OU	DOWN TO 45 DB(A)	DOWN TO 56 DB(A)	DOWN TO 60 DB(A)	DOWN TO 53 DB(A)	DOWN TO 53 DB(A)	DOWN TO 51 DB(A)	DOWN TO 62 DB(A)
AUXILIARY HEAT STRIPS AVAILABLE	YES (FIELD INSTALLED)	YES (FIELD INSTALLED)	YES (FIELD INSTALLED)	YES (FIELD INSTALLED)	YES (FIELD INSTALLED)	YES (FIELD INSTALLED)	YES (FIELD INSTALLED)
"PRE-CHARGED LENGTH"	31 FT.	15 3/8 FT.	15 TO 25 FT.	66 FT.	66 FT.	70 FT.	25 FT.
PIPE LENGTH (MIN/MAX)	10/100 FT.	15 / 150 FT.	15 / 100 FT.	16 / 164 FT.	16 / 164 FT.	16 / 165 FT.	10 / 213 FT.
MAX. PIPE ELEVATION	50 FT.	50 FT.	90 FT.	98 FT.	98 FT.	100 FT.	98 FT.